



Sykehusbygg HF

Vi bygger for pasientens helsetjeneste

Hva betyr industrialisering i teori og praksis?


Hvorfor engasjerer store byggherrer seg med dette?


Lars Abrahamsen

Om Sykehusbygg

- Startet i 2015
- Eies av de 4 regionale helseforetakene
- Oppdrag kun for helseforetak og regionale helseforetak
- Skal benyttes for alle prosjekt > 500 MNOK
- Hovedkontor i Trondheim og kontorer i Oslo, Stavanger, Kristiansand, Molde, Bodø
- Ca. 100 ansatte
 - Prosjektledere, klinisk personell/sykehusplanleggere, utstysplanleggere, ingeniører, arkitekter, økonomer, personell med spesialistkompetanse på spesialrom, fortidsminnevern, BIM

Prosjekter (utbygging, ombygging, analyser)





Ekstremt – Look to China!



20:23
designventurer.com

HOME NEWS PREFAB_RESEARCH R_LAB

Modular Construction: The future of High-rise building? And what about the jobs?

Posted by admin on April 1st, 2011

On March 16, 2011, [The New York Times](#) ran an article entitled "Prefabricated Tower May Rise at Brooklyn's Atlantic Yards". The gist of the story was that a major real estate developer had agreed to build apartments in an old shipyard, and had gained support for his bid from local trade unions based on his promise of thousands of union construction jobs.

Um, never mind.

Bruce C. Ratner is apparently now pursuing an alternative construction strategy using prefabricated building modules. His inspiration, it is said, was the video below.

Ark Hotel Construction time lapse building 15 storeys in 2 days (...)

Is this necessarily a bad thing? Figuring out how to build more buildings housing more people (or

SEARCH

DESIGN VENTURER ON TWITTER

DV OPEN RESEARCH CATEGORIES

Prefabrication - Retrofitting - Green

DV PREFAB CONTENT

NEWS (43)

- Community Development (3)
- Large Projects (2)
- Companies (16)
- Countries (14)
- Canada (2)
- China (2)
- Haiti (1)
- Japan (5)
- Philippines (2)
- Singapore (1)
- Sri Lanka (1)
- USA (1)
- For Buyers (1)
- Materials (1)
- MFP (2)

MCKINSEY GLOBAL INSTITUTE

REINVENTING CONSTRUCTION: A ROUTE TO HIGHER PRODUCTIVITY

FEBRUARY 2017

IN COLLABORATION WITH
MCKINSEY'S CAPITAL PROJECTS & INFRASTRUCTURE PRACTICE

EXECUTIVE SUMMARY

The productivity opportunity in construction



Construction matters for the world economy

... but has a long record of poor productivity



Construction-related spending
accounts for

13% of the world's GDP

...but the sector's annual productivity
growth has only increased

1% over the past 20 years


\$1.6 trillion of additional value added could be
created through higher productivity,
meeting half the world's infrastructure need

Construction is a sector of two halves

Fragmented specialized trades drag down
the productivity of the sector as a whole

Construction productivity by subsector
Value added per employee, indexed total sector=100, 2013

● % of construction value added



Action in seven areas can boost sector productivity by **50–60%**



- Reshape regulation
- Rewire contracts
- Rethink design
- Improve procurement and supply chain
- Improve onsite execution
- Infuse technology and innovation
- Reskill workers

5–10x productivity boost

possible for some parts of the industry by moving
to a manufacturing-style production system



MCKINSEY
GLOBAL
INSTITUTE

RESEARCH.
INSIGHT.
IMPACT.



7 anbefalte tiltak for å håndtere 10 rotårsaker til byggebransjens dårlige produktivitet


- Omforme forskrifter og øke åpenhet
- Omstrukturer kontraktsregime
- Rekonstruere planleggings og prosjekteringsprosessen
- Forbedre innkjøp og ledelse i leverandørkjeden
- Forbedre gjennomføring på byggeplass
- Implementer ny teknologi, nye produkter og avansert automatisering
- Omskolere arbeidsstyrken

Exhibit E5

Construction can catch up with total economy productivity by taking action in seven areas

Cascading effect

Regulation changes facilitate shifts in industry dynamics that enable firm-level levers and impact



¹ The impact numbers have been scaled down from a best case project number to reflect current levels of adoption and applicability across projects, based on respondents to the MGI Construction Productivity Survey who responded "agree" or "strongly agree" to the questions around implementation of the solutions.

² Range reflects expected difference in impact between emerging and developed markets.

Store gevinster – McKinsey&Company

There is an opportunity for parts of the construction industry to move to a production system—and boost productivity up to tenfold



Waste

Wasted Time in Construction is Out of Control.


The Construction Industry Institute (CII) published a report in 2004 comparing wasted time vs productive time in the manufacturing and the construction industry.

88% of time in manufacturing was found to be productive (value added) vs only 43 % of time spent in construction. This reports demonstrates that more than 50% of time spent on construction sites is waste (non value added).



Kilde: leanipd.com

Behov for langsiktighet



Fra skreddersøm og on-site til standardisering og off-site

Sykehusbygg

Byggmetodikk / industriell byggproduksjon



Plassbygd
(Tradisjonell
byggmetodikk)




«Flatpakket»
Separate moduler som settes
sammen på byggeplass:



Store rommoduler

Ulike tilnærminger til industrialisering



Begreper industrialisering

Produktindustrialisering

- Flytter grensesnittet fra byggeplassproduksjon til industripartner

Prosessindustrialisering

- Utvikler vareflyt og produksjon mer industrielt

Enfaglige leveranser

Flerfaglig leveranser




Modulær industrialisering

- Innenfor etablerte bransjeinndelinger

Systemisk industrialisering

- På tvers av etablerte strukturer

EDUCATION // SYSTEMS APPROACH



Prosess
og
logistikk

Komp
enfag

Komp
flerfag

Flate
enfag

Flate
flerfag

Rom
flerfag

Volum
flerfag

Ulike tilnærminger til industrialisering

OFF-SITE FABRICATION



- Benytter industripartnere for leveranser

NEAR-SITE FABRICATION

- Etablerer produksjon midlertidig i egnede nærliggende lokaler

ON-SITE FABRICATION

- Industriell byggeproduksjon



Industrialisering ved ulike entreprisemodeller

BH styrte delte E

- Industrieløsning bestemmes av BH og RG
- (SUS2023)

Total Entr


- Industrieløsning bestemmes av TE
- (SNR)

IPD

- Industrieløsning bestemmes i fellesskap
- (Tønsbergprosjektet)


Industrileverandør

- Industrieløsning bestemmes av ind.part
- (Nye Kirkenes)




DIFFERENT PLATFORM STRATEGIES

- Choice of platform strategy affects process structure and organization
- The business model changes with the platform strategy
- Difference in offer and company role




Litt om barrierer

Fragmentering i en moden byggebransje



Strukturelle hindringer for diffusjon av innovasjon i byggebrasjen



Kilde: Sheffer & Levitt, 2010

Kontraheringsprosess og kontraktstype



Industrialisering og innovasjon

- Er fagforeningsinteresser med på å bremse? Det er god akkord på å gjøre det på gamlemåten når hindringer ryddes av veien i forkant.
- Det gir mer arbeid lokalt med mer tradisjonelle løsninger.
- Nye måter øker risikoen og krever mer samhandling. Aktørene må ha tid til det og ha en økonomisk gulrot for å gjøre det.
- Individualisering krever relativt tidlig prosjektering i forhold til tradisjonell TE. Beslutningsvegring ødelegger fort mulighetene.

Bo Terje Kalsaas, uia

Et eksempel fra Denver, CO

A VALUE-BASED COST-BENEFIT ANALYSIS OF PREFABRICATION PROCESSES IN THE HEALTHCARE SECTOR: A CASE STUDY

Exempla Saint Joseph Heritage Project, Denver USA

$$B/C = \frac{[SiteBuilt\ Costs + Schedule\ Savings + Incident\ Costs\ Avoided]}{Prefabricated\ Costs}$$



Figure 2: Typical Prefabricated Bathroom Pod & Wall Panel



Figure 3: Typical Prefabricated Multi-Trade Rack & Patient Headwall

Sykehusprosjekt - 83000 m²

Table 3: Direct Cost Comparison Results

	Bathroom Pods	Wall Panels	MTRs	Headwalls	Total Prefab
Unit of Analysis:	Type 1 Bathroom Pod	15'H x 30'W Wall Panel	25'Lx8'Wx3'H MTR	Patient Room Headwall	All Prefab
Total Units:	440	346	166	376	1,328
Area (SF) / Unit:	51	284	200	72	N/A
Length (LF) / Unit:	N/A	19	25	N/A	N/A
Total Area (SF):	22,440	98,325	33,200	26,997	N/A
Total Length (LF):	N/A	6,458	4,150	N/A	N/A
Prefabrication Direct Cost	\$ 9,498,000	\$ 3,405,000	\$ 3,006,000	\$ 6,655,000	\$ 22,560,000
Site-Built Direct Cost	\$ 9,082,000	\$ 3,535,000	\$ 2,471,000	\$ 6,187,000	\$ 21,280,000
Total Direct Cost Delta	\$ 416,000	\$ (130,000)	\$ 535,000	\$ 468,000	\$ 1,280,000
% Direct Cost Delta	4.6%	-3.7%	21.7%	7.6%	6.0%

Table 4: Schedule Impact Comparison Results

	Bathroom Pods	Wall Panels	MTRs	Headwalls	Total Prefab
Total Baseline Duration (Work Days)	649	649	649	649	649
Additional Work Days due to Site-built	52	41	20	0	72
Total Duration for Site-Built (Work Days)	701	690	669	649	721
% Schedule Delay Avoided	7.4%	5.9%	3.0%	0.0%	10.0%
Avoided GC's Cost (rates not shown)	\$ 3,124,000	\$ 2,384,000	\$ 1,192,000	\$ -	\$ 4,275,000

Reelt oppnådd: 18%

Table 5: Labor Comparison Results

	Bathroom Pods	Wall Panels	MTRs	Headwalls	Total Prefab
Total Prefab Work-hours:					
Off-Site Prefab w-h	50,600	27,770	28,280	14,350	121,000
+ On-Site Prefab w-h	3,520	6,290	7,500	3,010	20,320
= Prefab w-h	54,120	34,060	35,780	17,360	141,320
Total Site-built Work-hours:					
Site-built w-h	81,820	39,210	31,070	18,700	170,800
Total Diverted Work-hours:					
Reduced On-Site Labor Hours	78,300	32,900	23,600	15,700	150,500
Diverted w-h	27,700	5,150	-4,710	1,340	29,480

Table 7: Benefit-to-Cost Ratio Analysis

B/C Analysis	Bathroom Pods	Wall Panels	MTRs	Headwalls	Total Prefab
Benefit					
Total Site-Built Cost Investment	\$ 9,082,000	\$ 3,535,000	\$ 2,471,000	\$ 6,187,000	\$ 21,280,000
+ Total Schedule Cost Savings	\$ 3,124,000	\$ 2,384,000	\$ 1,192,000	\$ -	\$ 4,275,000
+ Total Incident Cost Avoided	\$ 50,395	\$ 21,175	\$ 15,189	\$ 10,105	\$ 96,863
= Total Benefit	\$ 12,256,395	\$ 5,940,175	\$ 3,678,189	\$ 6,197,105	\$ 25,651,863
Cost					
Total Direct Prefab Cost	\$ 9,498,000	\$ 3,405,000	\$ 3,006,000	\$ 6,655,000	\$ 22,560,000
Benefit/Cost Ratio	1.29	1.74	1.22	0.93	1.14

EXEMPLA ST. JOSEPH HERITAGE PROJECT

PREFAB ELEMENT	SCHEDULE REDUCTION	INDIRECT COST SAVINGS	DIRECT COST	REDUCTION IN REQUIRED LABOR	DIVERTED OFF-SITE LABOR	SAFETY INCIDENTS REDUCED	JOBSITE PRODUCTIVITY LOSS PREVENTION
Exterior Wall Panels	41 Days	\$2.4 M	3.7% Savings	5,000 Hours	33,000 Hours	2	\$0.5 M
Bathroom Pods	52 Days	\$3.1 M	4.6% Premium	27,700 Hours	78,000 Hours	4	\$1.4 M
Multi-Trade Racks	20 Days	\$1.2 M	21.7% Premium	N/A	24,000 Hours	1	\$0.4 M
Patient Room Headwalls	0 Days	\$0	7.6% Premium	1,300 Hours	16,000 Hours	1	\$0.3 M
TOTAL	72 Days	\$4.3 M	6.0% Premium	29,500 Hours	150,500 Hours	7	\$2.6 M


LEAN // EVIDENCE

PROJECTS with **HIGH LEAN INTENSITY**
are **MORE LIKELY** to complete
AHEAD OF SCHEDULE & UNDER BUDGET
3X **2X**



Learn as a Team

Methods with Most Degree of Difference Between Usage



Timing of Key Stakeholder Engagement

